

SOP-P101: Pump P-101 Operation

Synthetic demonstration document for SIH. Not real MRPL operational data.

Purpose

Define general operating checks for a centrifugal pump used for process transfer.

Pre-start checks

Verify suction availability, discharge path, lubrication status, seal condition, instrument availability, and absence of visible leakage. Confirm required permits and site-specific safety controls.

Normal monitoring

Monitor temperature, pressure, flow, motor current and vibration. Compare readings with approved operating limits and historical trends.

Abnormal condition

If vibration, temperature, noise, leakage or other parameters show a significant abnormal trend, notify the responsible operator/engineer and follow the approved abnormal-operation procedure.

Shutdown

Follow the approved site shutdown sequence. Do not bypass interlocks or safety systems. Human authorization is required for operational decisions.